

BRAVO ST - 230 VAC


User Manual V7.4

BEYOND THE INVERTER

THE NEW GENERATION OF POWER CONVERTERS

- DUAL INPUT INVERTER

 The Commercial Power as default source
- AC BACKUP IN A DC ENVIRONMENT Leverage your existing DC infrastructure
- ONE STOP SHOP
 Wide output power range
- HARSHEST AC INPUT CONDITIONS
 Without compromising the quality of the AC output



Important Safety Instructions
Save these Instructions



Table of content

1.	CE+T at a glance						
2.	Abbr	viations	6				
	3.1 3.2 3.3 TSI 1 4.1	Safe mode	7 8 8 8 9 10 10				
_	4.4	Mix Mode & Walk-in-mode	10 11				
5.	5.1	Typical load	12 13 14				
	6.1 6.2 6.3 Acce	Inverter Module Automatic By-Pass Module Sub-rack ssories	16 16 16 17 18				
		7.1.1 Parameters setting	18 18 18 18 18				
8.	Brav	ST Shelves Installation Unpacking the system Mechanical Installation 8.2.1 System Dimensions 8.2.2 Fixing 8.2.3 Mounting Kit Electrical installation 8.3.1 Pre requisites 8.3.2 Terminations 8.3.3 Grounding 8.3.4 DC Input 8.3.5 AC Input (AC Input protection mandatory) 8.3.6 AC output.	19 19 19 19 20 21 21 22 23 23 23 23				



	0.5.0	4
9.	Human-Machine Interface	2
	9.1 Inverter module (Requires firmware V203 or higher)	4
	9.2 T2S	4
10.	System set up	2
	10.1 Communication Setting	4
	10.2 Menu access	3
11	Inserting/removing/replacing modules	,
	11.1 TSI Inverter	(
	11.1.1 Module Removal	(
	11.1.2 Inserting	(
	11.2 TSI By-Pass Module Replacement	(
	11.2.1 Removal	(
	11.2.2 Inserting	4
	11.3 T2S	4
	11.3.1 Removal	4
	11.3.2 Inserting	4
	11.4 Fan replacement	(
12.	Final check	;
13.	Commissioning	,
	13.1 Check list	(
1 /	Trouble Shooting and Defective Situations Fixing	,
14.	14.1 Trouble Shooting	
	14.2 Defective modules	(
	14.2.1 Replacing modules	,
	14.2.2 Return defective T2S interface	(
	14.2.3 Return defective shelf	,
	14.2.4 Return defective modules	4
15	Service	
16.	Maintenance Task	4



Release Note:

Version	Release date (DD/MM/YYYY)	Modified page number	Modifications
7.0	18/12/2014	-	First release of the Manual.
7.1	08/04/2015	-	Amendment and correction
7.2	27/02/2018	11, 13, & 15	Updated the information
7.3	13/04/2018	25	Updated configuration parameters
7.4	05/12/2019	27 & 28	Updated configuration parameters



CE+T at a glance

1. CE+T at a glance

CE+T Power designs, manufactures and markets a range of products for industrial operators with mission critical applications, who are not satisfied with existing AC backup systems performances, and related maintenance costs.

Our product is an innovative AC backup solution that unlike most used UPS's

- Maximizes the operator's applications uptime;
- Operates with lowest OPEX;
- Provides best protection to disturbances;
- Optimizes footprint.

Our systems are:

- Modular
- Truly redundant
- Highly efficient
- Maintenance free
- Battery friendly

CE+T puts 60+ years expertise in power conversion together with worldwide presence to provide customized solutions and extended service 24/7 - 365



Abbreviations

2. Abbreviations

TSI Twin Sine Innovation

EPC Enhanced Power Conversion

REG Regular

DSP Digital Signal Processor

AC Alternating current

DC Direct current

ESD Electro Static Discharge

MET Main Earth Terminal

MBP Manual By-pass

TCP/IP Transmission Control Protocol/Internet Protocol

USB Universal Serial Bus

PE Protective Earth (also called Main Protective Conductor)

N Neutral

PCB Printed Circuit Board

TRS True Redundant Structure
MCB Miniature Circuit Breaker

MCCB Molded Case Circuit Breaker

CB Circuit Breaker



Warranty and Safety Conditions

3. Warranty and Safety Conditions*

WARNING:

The electronics in the power supply system are designed for indoor, clean environment.

When installed in dusty and/or corrosive environment, outdoor or indoor, it is important to:

- Install an appropriate filter on the enclosure door, or on the room's air control system
- Keep the enclosure door closed during operation
- Replace the filters on a regular basis.

Important Safety Instructions and Save these Instructions.

- The inverter system/rack can reach hazardous leakage currents. Earthing must be carried out prior energizing the system. Earthing shall be made according to local regulations.
- Prior to any work conducted to a system/unit make sure that AC input voltage and DC input voltage is disconnected.
- CAUTION Risk of electric shock. Capacitors store hazardous energy. Do not remove cover until 5 minutes after disconnecting all sources of supply.
- CAUTION Risk of electric shock. This Inverter / UPS receives power from more than one source. Disconnection of the AC source and DC source is required to de-energize this unit before servicing.
- Maximum operating ambient temperature is 40° C (104° F).
- AC and DC circuits shall be terminated with no voltage / power applied.
- Some components and terminals carry high voltage during operation. Contact may result in fatal injury.
- Warning labels must not be removed.
- Never wear metallic objects such as rings, watches, bracelets during installation, service and maintenance of the product.
- Insulated tools must be used at all times when working with live systems.
- When handling the system/units pay attention to sharp edges.
- ESD Strap must be worn when handling PCBs and open units.
- The inverter system/rack is not supplied with internal disconnect devises on input nor output.
- The inverter rack is a dual input power supply. The complete system shall be wired in a way that both input and output leads can be made powerless in a single action.
- REG systems can be seen as independent power sources. To comply with local and international safety standards N (output) and PE shall be bonded.
- EPC system that have no AC input wired and connected to comply with local and international safety standards N (output) and PE shall be bonded. The bonded between N output and L must be removed once the AC input is being connected.
- The safety standard IEC/EN62040-1-1 requires that, in case of output short circuit, the inverter must disconnect in maximum 5 seconds. However, if the parameter is set at a value > 5 seconds, an external protection must be provided in order that the short circuit protection operates within 5 seconds. Default setting is 60s.
- The equipment must be installed and commissioned by skilled technicians according to instructions in this manual.

^{*} These instructions are valid for most CE+T Products/Systems. Some points might however not be valid for the product described in this manual



Warranty and Safety Conditions

- Local regulations must be adhered.
- The manufacturer declines all responsibilities if equipment is not- installed according to -instructions herein -by skilled technician -according to local safety regulation.
- Warranty does not apply if the product is not installed, used and handled according to the instructions in the manuals.
- CE+T cannot be held responsible for disposal of the Inverter system and therefore the customer must segregate and dispose the materials which are potentially harmful to the environment, in accordance with the local regulations in force in the country of installation.
- If the equipment is dismantled, to dispose of the products it consists of, you must stick to the local regulations in force in the country of destination and in any case avoid causing any kind of pollution.
- System is designed for installation in an IP20 or IP21 environment. When installed in a dusty or humid environment, appropriate measures (air filtering ...) must be taken.

3.1 Handling

- The cabinet shall not be lifted using lifting eyes.
- Remove weight from the cabinet by unplugging the inverters. Mark inverters clearly with shelf and position for correct. This is especially important in three phase configurations.
- Empty inverter positions must not be left open. Replace with module or dummy cover.
- All illustrations in the manual are for general reference, refer to the technical drawing which is received along with the system for exact information.

3.2 Surge and transients

The mains (AC) supply of the modular inverter system shall be fitted with suitable Lightning surge suppression and Transient voltage surge suppression for the application at hand. Manufacturer's recommendations of installation shall be adhered. It is advisory to select device with alarm relay for function failure.

Indoor sites are considered to have a working lightning surge suppression device in service.

- Indoor sites Min Class II.
- Outdoor sites Min Class I + Class II or combined Class I+II.

3.3 Other

Isolation test must not be performed without instructions from the manufacturer.

To download the latest documentation and software, please visit our website at www.cet-power.com.




TSI TECHNOLOGY

4. TSI TECHNOLOGY 1

Inverter modules carrying the TSI logo and the EPC mark are triple port converters (AC in, DC in, AC out). Sinusoidal output is converted from Mains or/and DC.

The block diagram here below gives an explicit description of the topology and operation.



The module is built around the following sub-converters

- AC to DC at input
- DC to DC at input
- DC to AC at output

The energy can flow either from the AC source or the DC source under the control of the local DSP controller. Thanks to internal energy buffering, the output sine wave is constant and disturbance free regardless of the active source.

The BOOST functionality multiplies the nominal current for a period of 20ms(max) in the event of down stream current surge. The upstream breakers do not have to be oversized to prevent tripping. After the boost has been activated or if the AC input is not present the overload capacity is 150% for 15 seconds regardless of the source currently used.

The TSI works according to True Redundant Structure (TRS) that features decentralized and independent logic, redundant communication bus and three internal levels of disconnection to isolate a module after internal failure.

The functionality is included in every inverter module. Running them in parallel provides a modular system with, no single point of failure, always conditioned output, high system efficiency and 0ms source transfer time.

¹ I Information and data given in this chapter intend to for an overview on the technology. Detailed features and parameters for each individual module type of the range may differ and should be referred in the dedicated data sheet.



TSI TECHNOLOGY

4.1 On-line Mode

DC is the primary source of supply whilst Mains (AC) works as the secondary source of supply. Switching time between DC input and AC input is 0ms (source transfer). The power delivered by the DC source (usually a battery, but it could be any other type of DC generator) is converted to provide regulated and transient free power to the load. In case of short circuit at the load side, the boost is automatically, timely and energized for a specific duration to trip downstream protective devices.

4.2 Safe mode

Safe mode uses DC as primary source of supply while Mains (AC) is in standby.

Mains (AC) is normally disconnected through internal inlet relay and is only connected when down stream clearance is required (boost) or if DC is unavailable.

The transfer between DC and AC results in typical transfer time of 10ms.

Typically the safe mode is used in extremely harshed environments such as railways. Under such conditions it provides extra isolation against disturbances carried by the Mains.

4.3 EPC-mode

Mains input (AC) is the primary source whilst DC works as backup.

The TSI is designed to operate on Mains on permanent basis and to deliver output voltage conditioned with low THD.

There is no physical difference on the output sine wave whether the source is AC (or) DC. If the Mains is out of tolerance or goes down, the converter seamlessly switches to DC and the converter operates in "Back-up mode" (Switching time back and forth is 0 ms).

As soon as the Mains returns in to valid range, the EPC mode is automatically resumed.

The EPC mode offers higher efficiency (up to 96% depending on the model) without compromising the purity of the output sine wave.

NOTICE: REG modules:

Inverter modules carrying the TSI logo together with REG mark are modules working only with DC input . Sinusoidal output is converted from DC and the module operates as a traditional inverter. EPC mode and the boost are not available with REG modules.

4.4 Mix Mode & Walk-in-mode

Under some circumstances DC and AC source can be combined. The sequence is defined by a user selectable set of parameters, start, control and exit are fully automatic .

A specific example of Mix-mode is the Walk-in mode where the transfer from DC source to AC source is ramped up within a fix and adjustable period of time.

Setting for Walk -in -Mode and Mix Mode can be made through the T2S supervisor configuration file. See section 10, page 29 for more information on T2S supervisor.



TSI TECHNOLOGY

4.5 By Pass Mode

The automatic by pass is engaged in case of following condition

- AC input is present and 1 BRAVO TSI Module failure if no redundancy configured OR only one module installed OR
- AC input is present and **2 BRAVO TSI** module failure if one module redundant has been configured.

The automatic by pass IS NOT AVAILABLE if:

- No AC input is present
- AC output LOAD exceed 5 kVA



Description

5. Description

Bravo ST has been designed to give quality power, ease of use, and reliability. It provides up to 4000 watts (Bravo ST 5 KVA) or up to 2000 watts (Bravo ST 2.5 KVA).

In normal operation:

- AC input present the TSI module will operate in EPC mode.
- AC input fail the TSI module will switch to DC (battery) and continue to feed the load.
- DC input fail the system operate on AC input.


TSI module fail (N+1):

- If N+1 configuration selected the second module will continue to feed the load.
- If the second module fail the system will switch to AC through the automatic by pass to allow module replacement.

TSI module fail (N no redundancy):

If one module fail the BRAVO ST will switch to AC through the automatic by pass to allow module replacement.

All part of the BRAVO ST (Inverter modules and by pass module) are hot swappable without shut down of the AC output.



Warning:

If all modules fails and AC input not present, the system will stop to prevent "backfeed" protection upstream.




Description


Bravo ST 230 VAC is a standalone Inverter with following capacities.

- Standalone model 5000 VA (3000VA in 24VDC).
- Standalone model 2500 VA, with Redundancy (1500VA for 24VDC).
- Standalone model 2500 VA, without Redundancy (1500VA for 24VDC).

230Vac and 48Vdc as Input and 230Vac as Output fitted with Enhanced Power Conversion (EPC) mode (Other DC input voltage 24VDC, 110VDC, 220VDC will be available).



Front View



Rear View

5.1 Typical load

- Resistive.
- Inductive and resistive.
- Capacitive and resistive.



Description

5.2 Specifications

Model	ST - 24 / 230	ST - 48 / 230	ST - 110 / 230	ST - 220 / 230			
GENERAL	GENERAL						
Part number	S32P72E0202S	S32P73E0202S	S32P75E0202S	S32P76E0202S			
EMC (immunity)	EN 61000-4-2 / El		i-4-4 / EN 61000-4-5 / E 0-4-8	EN 61000-4-6 / EN			
EMC (emission) (class)	EN 55022 (A)	EN 55022 (B)	EN 55	022 (B)			
Safety		IEC 60950 / EN620)40-1 / EN62040-2				
Cooling / Isolation / Audible noise		Forced / Doubled / <	< 65 dBA at 1 meter				
MTBF		240 000 hrs	(MIL-217-F)				
Efficiency (Typical): Enhanced power conversion / on line	> 95.5% / > 89.5%	96%	/ 91%	96.5% / 92.5%			
Dielectric strength DC/AC		4300) Vdc				
RoHS 6		Com	pliant				
Vibration	GR63 office vibratio		ansport vibration 5-100 Drop test	Hz 0.5 g 100 to 500			
Operating conditions			an IP20 or IP21 environn nment, appropriate meas e taken.				
Altitude above sea without de-rating	<	1500 m / derating > 15	500 m – 0.8 % per 100	m			
Ambient / storage temperature / relative humidity	-20	0 to 50 ° C / -40 to 70 °	C / 95 %, non-condens	ing			
Material (casing)	asing) Coated steel-ALU ZINC						
AC OUTPUT POWER	BRAVO ST 1500 - ST 3000 BRAVO ST 2500 - ST 5000						
Nominal Output power (VA)	1500 / 3000 2500 / 5000						
Nominal Output power (W)	1200 / 2400 2000 / 4000						
Short time overload capacity	150) % (15 seconds) 110 %	permanent within T° ra	nge			
Admissible load power factor	F	Full power rating from 0	inductive to 0 capacitive	е			
Internal temperature management and switch off	Above 50°C ambia	nt T° derating up to 65°	C. Automatic restart wit	h hyteresis +/- 5°C			
DC INPUT SPECIFICATIONS							
Nominal voltage (DC)	24 V	48 V	110 V	220 V			
Voltage range (DC)	19 – 35 V	40 - 60 V	90 - 160 V	170 - 300 V			
Nominal current at nominal DC voltage and max power W	56 A @ 1200 W/ 1500 VA 112 A @ 2400 W/ 3000 VA	46 A (at 48 Vdc and 2000 W output) 93 A (at 48 Vdc and 4000 W output)	20.2 A (at 110 Vdc and 2000 W output) 41 A (at 110 Vdc and 4000 W output)	10.1 A (at 220 Vdc and 2000 W output) 20,5 A (at 220 Vdc and 4000 W output)			
Maximum input current (for 15 second) / voltage ripple	84 A / < 100 mV rms	84 A / < 2 mV Psopho	29 A / < 200 mV rms	14.9 A / < 200 mV rms			
Input voltage boundaries	Input voltage boundaries User selectable with T2S interface min and max value						
AC INPUT SPECIFICATIONS							
Nominal voltage (AC)	220 Vac / 230 Vac / 240 Vac						
Voltage range (AC)		150-	265 V				



Description

Brownout	150 to 185 V linear derating 150 VA/120 W per 10 Vac for 2500 VA model and 300 VA/ 240 W for 5000 VA model		
AC input range min and max value	Adjustable between 150 Vac and 265 Vac (fixed hysteresis 10 Vac)		
AC input power factor (EPC operation mode)		> 99%	
Frequency range (selectable) / synchronization range	50 - 60 Hz / range 47 - 53 Hz / 57 - 63 Hz		
AC OUTPUT SPECIFICATIONS			
Nominal voltage (AC*)	230 V	/ 220V / 240 Vac adjustable (default 230 Vac - 50 Hz)	
Frequency / frequency accuracy		50 - 60 Hz / 0.03 %	
Total harmonic distortion (resistive load)		< 1.5 %	
Load impact recovery time		0.4 ms	
Turn on delay	20 s to 40 s depending on the number of module installed		
Nominal current. Protected against reverse current	6.6 A	10.9 A	
Crest factor at nominal power With short circuit management and protection	2.8 : 1	3:1	
Short circuit clear up capacity	10 x In for 2	0 msec - Available while Mains is available at AC input port With magnitude control and management	
Short circuit current after clear up capacity		2.1 In during 15 s and 1.5 In after 15 s	
IN TRANSFER PERFORMANCE			
Max. voltage interruption AC to DC module - Module to bypass	0 ms between DC to AC and AC to DC / <10 ms between BRAVO mode and automatic bypass		
SIGNALING & SUPERVISION			
Display	Synoptic LED		
Alarms output / supervision	Dry contacts on shelf / Standard USB port and MODBUS on T2S, optional : Candis Display / Candis TCP-IP		



Bravo ST Components

6. Bravo ST Components

6.1 Inverter Module

Bravo: 24 VDC 1500 VA-230 VAC.

48 VDC 2500 VA-230 VAC.

60 VDC 2500 VA-230 VAC.

110 VDC 2500 VA-230 VAC.

220 VDC 2500 VA-230 VAC.



- The BRAVO module shall have software version V203 or higher to operate with BRAVO ST.
- The TSI Bravo is a 2500VA/2000W converter based on the TSI technology (see section 4). 1500VA/1200W for 24VDC
- The TSI inverter modules are hot swappable and hot pluggable. They are featured with self setting capabilities for easy plug-and-play operation.
- LED's on module front plate display the status of converter and output power.
- Inverter modules can be combined to build any single or multi-phase structures.
- The inverter modules are equipped with soft start.
- The fan is equipped with alarm and run time meter. It is field replaceable.
- 17.13" (D) x 4.02" (W) x 3.46" (H). [435mm (D) x 102mm (W) x 88mm (H)].
- 11 lbs [5 kg].

6.2 Automatic By-Pass Module

- 5000 VA By-Pass.
- Will automatically connect the load to the commercial grid (if available) when one or both inverter modules are not available.
- Transfer time <10ms.</p>
- Hot pluggable: can be removed without shutting down the system provided that sufficient inverter modules are present and running.





Bravo ST Components

6.3 Sub-rack

- The BRAVO ST 230 VAC shelf shall be integrated in min 600mm deep cabinets, 19 Inch / ETSI mounting.
- The BRAVO ST 230 VAC shelf houses maximum two (2) inverter modules and one (1) T2S interface. Maximum 5KVA per shelf.
- The Bravo ST 230 VAC shelf is designed with individual DC input, common AC input and common AC output.
- Optional rear cover can be provided for enhanced safety in cabinet.
- 18.9" (D) x 19" (W) x 2U (H). [480mm (D) x 19" (W) x 2U (H)].
- 13 lbs [6 Kg] empty.





Accessories

7. Accessories

7.1 T2S-2C Interface

The T2S is an interface giving access to the TSI modules that are connected together in any TSI systems.

The T2S doesn't perform any control or management of the TSI system. It can be removed, replaced or moved to another live system without affecting neither the original TSI system operation nor the target system.

7.1.1 Parameters setting

The T2S interface is featured with a USB connector at the front. Connected to a laptop, it enables TSI system settings, modules and phase assignments, and other various adjustments to allow TSI best fit with actual site conditions. (Operation of T2S is described in separate manual available on request).

7.1.2 System diagnostic and troubleshooting

The T2S is featured with built-in user interface to allow on-line diagnostic through laptop.

Installers and maintenance technicians should always carry proper laptop to access/reconfigure the system on site.

7.1.3 On-the-fly monitoring

The T2S is featured with

- 3 outgoing alarms contacts.
- 2 digital inputs.
- MOD bus.
- CAN bus (optional).
- Alarm monitoring.
- Record the latest 200 events. FIFO.

7.2 Surge Arresters

The mains (AC) supply of the modular inverter system shall be fitted with suitable Lightning surge suppression and Transient voltage surge suppression for the application at hand. Manufacturer's recommendations of installation shall be adhered. It is advisory to select a device with an alarm relay for function failure.

Surge arrestor(optional) is installed in the system.

Indoor sites are considered to have a working lightning surge suppression device in service.

- Indoor sites Min Class II.
- Outdoor sites Min Class I + Class II or combined Class I+II.





Bravo ST Shelves Installation

8. Bravo ST Shelves Installation

8.1 Unpacking the system

BRAVO ST is packed in a wooden box.

Modules are packed seperately. They are normally marked to be replaced in the right slot


Module packing material shall be taken apart and stored in case of return under warranty. Unproper packing may void the warranty.

The packing material of the TSI system is recyclable.

8.2 Mechanical Installation

- Sub-rack is preferable mechanically fixated without modules.
- T2S-2U can be left in the sub-rack.
- Min two (2) fixing screws per side of the sub rack.
- Fixing holes for Inch and ETSI mounting frames.
- System is designed for installation in an IP20 or IP21 environment. When installed in a dusty or humid environment, appropriate measures (air filtering ...) must be taken.

8.2.1 System Dimensions



8.2.2 **Fixing**

A full range of accessory is ready made to allow easy integration of the TSI in almost any kind of standard cabinets. Among other we provide fixing set for:

- 19" 600mm depth cabinets (most standard solution, which is supplied by default shown here).
- 19" 800mm depth cabinets.
- ETSI 600mm depth cabinets.




Bravo ST Shelves Installation

8.2.3 Mounting Kit

Make sure that you have received the proper accessories for Bravo ST 230 VAC which consist of 1 pair of 19" kit as shown following Figure.

The fixing brackets, together with the sliders, allow for different cabinet depths.




Slider - 2 Nos.

Brackets - 4 Nos.

Latches - 2 Nos.

Bolts - 12 Nos.

Removable nuts - 12 Nos.




Assemble the sliders and adjust the length to suit the mounting depth

Fix cage nuts in the cabinet front and rear frame of the left and the right side

Fix the left and right slider of the cabinet with the supplied mounting screws.




Bravo ST Shelves Installation



Fix cage nuts in the mounting frame

Assemble the mounting bracket in a suitable position.

Slide the shelf in position and fix the shelf with the supplied mounting screws



Finished

8.3 Electrical installation

8.3.1 Pre requisites

- The sub –rack have markings for all terminations.
- All cables shall be rated at Min 90 deg C.
- Electrical terminations shall be tightened with 5Nm.
- All connection screws are M5 x 12mm.
- DC Input-Individual (per module), observe polarity.
- AC Input / AC output –Common (per shelf), respect phases.




Bravo ST Shelves Installation

- Wire all positions in the sub-rack for future expansion.
- Input AC / Output AC / Input DC / Signal cables shall be separated
- Cable crossings shall be done in 90 deg angles.
- It is recommended to install appropriate breaker at AC input and place a warning label near the breaker stating message as "ISOLATE UNINTERRUPTIBLE POWER SUPPLY (UPS) BEFORE WORKING ON THIS CIRCUIT".

8.3.2 Terminations

Rear Side of Bravo ST 230 VAC terminations are clearly marked in the following figure




8.3.3 Grounding

"PE CHASSIS GROUND"

PE Chassis ground shall be wired to MET or distributed earth bar connected to MET

Main protective conductor(PE) connection is made to the X2(AC IN) terminal block marked with symbol for identification.



PE must be terminated even if commercial Mains is not available and shall be connected to building or main panel ground. Recommended Cable cross section is the size equal(min) to Neutral cable cross section. Adhere to local regulations.

Ground has to be connected in accordance with local code.



Bravo ST Shelves Installation

8.3.4 DC Input

Model	CB per inverter module	Cable, min	Connector	Torque
24 VDC & 48 VDC	63 A	2 x 4 AWG (16 mm ²)		
60 VDC	50 A	2 x 6 AWG (10 mm ²)	ME	E Nm
110 VDC	25 A	2 x 10 AWG (4 mm ²)	M5	5 Nm
220 VDC	16 A	2 x 12 AWG (2.5 mm²)		


8.3.5 AC Input (AC Input protection mandatory)

Model	CB per shelf	Cable, min	Connector	Torque
230 VAC (5 KVA)	2p 25 A	3 x 10 AWG (4 mm ²)	ME	F Nm
230 VAC (2.5 KVA)	2p 16 A	3 x 12 AWG (2.5 mm ²)	M5	5 Nm

8.3.6 AC output

Model	Cable, min	Connector	Torque
230 VAC (5 KVA)	3 x 10 AWG (4 mm ²)	ME	E Nm
230 VAC (2.5 KVA)	3 x 12 AWG (2.5 mm ²)	M5	5 Nm

8.3.7 Signalling





Bravo ST Shelves Installation

Relay characteristics (Selectable, Major, Minor)

Switching power 60W

Rating 2A at 30VDC / 1A at 60VDC

■ Max wire size 1mm²


Digital input characteristics (Digital In 1 / 2)

■ Signal voltage +5VDC (galvanic insulated)

Max wire size 1mm²

8.3.7.1 Remote ON/OFF

Note: The system is by default equipped with a connection between pin 3 and 2. If remote ON/OFF is not used the strap shall remain. Should the remote ON/OFF be used the strap must be replaced with a changeover contact or emergency button.





- The remote ON/OFF switch the output AC OFF.
- Input AC and input DC is not affected by the remote ON/OFF.
- The remote ON/OFF requires changeover contacts, one input opens as the other close. If both transitions are not picked up the status is not changed.
- Digital input characteristics (Remote On/Off)
 - Signal voltage +5 VDC (galvanically insulated)
 - Max wire size 17 AWG (1mm²)

Functional table for remote ON/OFF function

#	Pin 1-3	Pin 2-3	Status	Indication
1	Open	Open	Normal operation	All (Green)
2	Closed	Open	OFF	AC output (OFF) AC Input (Green) DC Input (Green)
3	Open	Closed	Normal operation	All (Green)
4	Closed	Closed	Normal operation	All (Green)

Warning: If remote ON/OFF not used, pin 2 and 3 MUST be bridged together!







Bravo ST Shelves Installation

8.3.8 Rear cover

- The rear cover provides IP 20 to the rear terminations when required
- The rear cover is snapped in position in the rear of the sub-rack.
- Remove material using a pair of side cutters to allow cables enter and exit.
- The rear cover is ordered separately.



Connect Cables



Cut holes to allow cable access




Clip rear cover in place



Human-Machine Interface

9. Human-Machine Interface

9.1 Inverter module (Requires firmware V203 or higher)



Inverter Status LED	Description	Remedial action
OFF	No input power or forced stop	Check environment
Permanent green	Operation	
Blinking green	Converter OK but working conditions are not fulfilled to operate properly	
Blinking green/orange alternatively	Recovery mode after boost (10 In short circuit condition)	
Permanent orange	Starting mode	
Blinking orange	Modules cannot start	Check T2S configuration or Module with wrong firmware. Need firmware V203 or higher.
Blinking red	Recoverable fault	
Permanent red	Non recoverable fault	Send module back for repair

	indancy not counted)					
<5%	5% to 40%	40 to 70%	80 to 95%	100%	100% = overload	Output Power (redundancy not counted)
×	×	×	=	=	=	
×	×	=	=	=	=	Status output power LED
_	_	_	×	_	_	
1B	1P	2P	2P	3P	3B	Behaviour (B = blinking - P permanent)



Human-Machine Interface

9.2 T2S

T2S has two new parameters.

Parameter	Parameter Name	Values	Description
420	ST Module Number	0, 1 or 2	Define the total number of BRAVO modules in the configuration. (Including Redundancy module)
421	ST Module Redundancy	0 or 1	Define the number of Redundancy module in the configuration.

Note: The BRAVO module V203 or higher those parameters appear automatically and T2S is pre configured in factory.

If you change T2S you must be sure to configure the parameter correctly prior to insert in the BRAVO ST

Alarm indication on T2S (Urgent / Non Urgent / Configurable)

- Green: No alarm - Red: Alarm


- Flashing Exchanging information with inverters (only Configurable alarm)

Outgoing alarm relay delay

- Urgent- Non urgent60 seconds delay30 second delay

Parameter setting via Laptop.

Factory default according to list of set values.



The following BRAVO ST configuration parameters are :

1. BRAVO ST - 5KVA - No redundancy

;01; ;Number of module in phase 1 ; ;2; ;; ;21; ;Amount of redundancy in phase 1 ; ;0; ;; ;420; ;ST Module Number ; ;2; ;; ;421; ;ST Module Redundancy ; ;0; ;;

2. BRAVO ST - 2.5 KVA - No redundancy

 ;01;
 ;Number of module in phase 1
 ; ;1;
 ;;

 ;21;
 ;Amount of redundancy in phase 1
 ; ;0;
 ;;

 ;420;
 ;ST Module Number
 ; ;1;
 ;;

 ;421;
 ;ST Module Redundancy
 ; ;0;
 ;;



Human-Machine Interface

_						
2	RRAV/N	SΤ	- 25	$KV\Delta =$	1 _ 1	redundancy
U.	יטארוט	OI.	- 2.0	1111	171	Touullualiov

;01;	;Number of module in phase 1	;	;2;	;;
;21;	;Amount of redundancy in phase 1	;	;1;	**
;420;	;ST Module Number	;	;1;	;;
:421:	:ST Module Redundancy	:	:1:	::



System set up

10. System set up

Bravo ST 230 VAC System is delivered with default set of parameters referred as factory settings.

Upon various site operating conditions or Site Manager requirements some parameters might have to be adjusted.

Refer to "TSI T2S 120VAC User Manual Vx_x" for detailed description of system status reading and changing as well as parameter adjustment.

- Parameter set up requires Hyper terminal installed on laptop
- USB cable type A to B (not included)
- T2S driver "CET_T2S.inf" installed on laptop.
- Available for download:
 - On my.CET for direct customers, in the "Document" section.
 - At the following URL for everyone else: http://www.cet-power.com/uploads/Driver_T2S/Driver_T2S_for_Windows_and_hyperterminal.zip.
- Read T2S manual for detailed setup.

10.1 Communication Setting

Bits per second 115200


Data bits 8

Parity None

Stop bits 1

Flow control None

Remark: Refer to document XXXX for detailed system setting and operation.





System set up

10.2 Menu access

Root Menu

- 1 > System configuration
 - 0 > Return to previous menu
 - 1 > Send config file to T2S
 - 2 > Read config file from T2S
 - 3 > Restore default settings (no more available since version 2.5)
 - 4 > Restore factory settings (no more available since version 2.5)
- 2 > System information's selection
 - 0 > Return to previous menu
 - 1 > Module information's 0 > Return to previous menu
 - 1 > Variables set 1 2 > Variables set 2 3 > Variables set 3
 - 4 > Variables set 4
 - > Variables set 4

 _ Nevt r
 - + > Next page - > Previous page
 - 2 > Phase information 0 > Return to previous menu
 - 1 > Variables set 1 2 > Variables set 2 3 > Variables set 3
 - 3 >Groups information 0 >Return to previous menu
 - 1 > Display AC group information 2 > Display DC group information
 - 4 > Alarms information 0 > Return to previous menu
 - 1-1 > Page selection
 - 5 > History of the log display 0 > Return to previous menu 1-14 > Page number selection
 - 1-14 > Page number selec
 - 16 > Clear log 17 > Save log to a file
 - 6 > Module errors information
- 0 > Return to preceding menu1-32 > Detailed Modules errors

- 3 > System actions selection
 - 0 > Return to previous menu
 - 1 > System actions
- 0 > Return to index
- 1 > Turn ON system
- 2 > Turn OFF system
- 3 > Change Date and time setting
- 2 > Inverter Module action 0 > Return to previous menu
 - 1-4 > Page number selection
 - 5 > Identify selected Module
 - 6 > Turn ON selected Module
 - 7 > Turn OFF selected Module
 - 8 > Change address of sel. Module
 - 9 > Change phase of selected Module
 - 10 > Automatic address assignment
 - 11 > Change DC group of selected Module
 - 12 > Change AC group of sel. Module
 - 13 > Notify changed fan of sel. Module
 - + > Increment selector - > Decrement selector
- 3 > T2s actions 0 > Return to index
 - 1 > Force refresh of configuration texts and constants
 - 2 > Force refresh of events description texts

- 4 > Security Access
 - 0 > Return to index
 - 1 >Enable Password protection



Inserting/removing/replacing modules

11. Inserting/removing/replacing modules

11.1 TSI Inverter

- The TSI inverter module is hot swappable. BRAVO ST operate with module having firmaware V203 or higher.
- When a new module is inserted in a live system it automatically takes the working set of parameters.
- When a new module is inserted in a live system it is automatically assigned to the next available address.
- While swapping the modules, power to load will be vary depending upon the models and are listed below.

Note:

Before swapping Inverter module, make sure the commercial grid is available to prevent any shut down of the AC output voltage.

The commercial grid shall be within the limit in voltage (195 Vac to 250 Vac) and frequency between 47,5 Hz to 52,5 Hz for 50Hz nominal and 57,5Hz to 62,5 Hz for 60Hz nominal.

If the load is supplied by "relay box" and the AC commercial input is not within the range (voltage and frequency) please DO NOT INSTALL NEW module. Risk of shutdown of the LOAD is present !!!

Module inserted in BRAVO ST with firmware below V203 cannot be used. They will not operate properly and will heat up abnormally.

- BRAVO ST 5000VA (3000VA in 24V) 2 Inverter Modules present + By Pass Module
 - Any one or both Inverter Modules can be removed or added.
 - When, either one or both Inverter Modules are replaced the AC output will be transferred to the AC commercial grid through the By-Pass Module.
- Bravo ST 2500 VA with Redundancy (2 Inverter Modules present + By Pass Module)
 - Any one or both Inverter Modules can be removed or added.
 - If one Inverter Module is removed, the load is supplied from the redundant Inverter Module.
 - If both Modules are removed, the load will automatically connect to grid through the By Pass Module.
- Bravo ST 2500 VA without Redundancy (One Module present + By Pass Module)
 - The Inverter Module can be removed or added.
 - When the Module is removed, the load will automatically connect to grid through the By Pass Module.




Inserting/removing/replacing modules


11.1.1 Module Removal

Notice: When one or several inverter modules is/are removed, live parts become accessible. Replace module with dummy cover without delay.


- Inverter module is not switched off when opening the handle. The handle only hooks the module to the shelf.
- Use a screw driver to release the latch of the handle.
- Open the handle and Pull the module out.
- Replace with new module or blind unit.



A) Use screwdriver to release the latch




B) open the cover completely




C) Use the cover as a handle to remove the module

11.1.2 Inserting


- Check module compatibility (DC Voltage!)
- Use a screw driver to release the latch of the handle.
- Open the handle and Push firmly until the unit is properly connected.
- Close the cover and latch in position.



A) Slide the module in



B) Push firmly till the connection is properly engaged



C) Close the cover and latch the module in place if too hard redo step B

Once the module is properly insert and locked it will restart automatically and the load will be transferred from the by-pass module to the inverter. The sequence might take 10 to 40 seconds.




Inserting/removing/replacing modules

11.2 TSI By-Pass Module Replacement

11.2.1 Removal

Note: Before replacing the By-Pass Module please make sure the inverter module are in operation and both AC input and DC input source are available.



Unscrew the screw in anti clock wise



Place Handle in Horizontal Position



Using Handle, gently remove By-Pass Module from the shelf



Place the By-Pass Module in Flattened Surface

11.2.2 Inserting




Take a new By-Pass Module



Close the handle in vertical position



Using Handle, gently push By-Pass Module into the shelf



Tight the screw in clock wise




Inserting/removing/replacing modules

11.3 T2S

11.3.1 Removal

- Use a small screw driver to release the latch keeping the T2S in position.
- Pull the T2S out.





11.3.2 Inserting


Push the T2S firmly in place until the latch snaps in position.

11.4 Fan replacement

The FAN life is approx 60.000 (Sixty Thousand) hours. The inverter modules have fan runtime meters and fan failure alarm. Fan failure can result from failing fan or driver circuit.

- Let the module rest at least 5 minutes prior to initiating work.
- The inverter front must be removed. Use a blunt tool to depress the latches on the module side fixing the front to the module.
- Remove the fan and unplug the supply cord.
- Replace with new fan and connect supply cord
- Replace front, make sure that the front latch properly.
- Plug in
- Check fan for operation
- Access T2S and reset the fan run time alarm from within the action menu.
- Once the FAN is replaced and module installed back in your system, You will need to clear the FAN alarm of the module.

 This can be done through the T2S menu 3 Action then 2 inverter action then 13 Notify change FAN.
- Refer to T2S manual for more details.





Final check

12. Final check

- Make sure that the sub-rack/cabinet is properly fixed to the cabinet/floor.
- Make sure that the sub-rack/cabinet is connected to Ground.
- Make sure that all DC and AC input breakers are switched OFF.
- Make sure that all cables are according to recommendations and local regulations.
- Make sure that all cables are strained relived.
- Make sure that all breakers are according to recommendation and local regulations.
- Make sure that DC polarity is according to marking.
- Re tighten all electrical terminations.
- Make sure that no inverter/controller positions are left open.
- Cover empty inverter positions with dummy cover.
- Make sure that the Remote ON/OFF is appropriately wired according to local regulations.
- Make sure that the point of AC supply meets local regulations.



Commissioning

13. Commissioning

The DC breaker is a protection device. Modules are plugged in a system and DC breaker is then engaged. Please make sure the corresponding DC breaker is engaged in the ON position. Failure to observe this rules will result not to have all module operating when running on DC and have module failure when AC input recover from fault condition.

Installation and commissioning must be done and conducted by trained people fully authorized to act on installation.

It is prohibited to perform any isolation test without instruction from manufacturer.

Equipments are not covered by warranty if procedures are not respected.



Commissioning

13.1 Check list

DATA							
Date							
Performed by							
Site							
System serial number							
Module serial numbers							
T1S/T2S serial number-Specify T1S/T2S							
ACTION	OK/ N.OK						
Unplug all inverters except one inverter per phase (Just pull off the inverter from the shelf, to interrupt electrical contacts)							
Check the commercial AC before closing the AC input breaker.							
Switch ON the commercial AC and switch OFF AC output breaker.							
Check if inverters are working (Green led)							
Check the DC power supply and switch ON the DC breakers							
Plug in all inverters one by one							
Check output voltage (on bulk output or on breaker)							
Check if inverters are working properly							
Check if system has no alarm (Disable the alarm if any)							
Read configuration file and review all parameters. Some parameters must be adapted according to the site (LVD, load on AC, AC threshold level)							
Switch OFF ACin and check if system is working on DC							
Switch ON ACin and check if system correctly transferred load on AC							
Switch OFF system and start on AC only							
Switch OFF system and start on DC only							
Remove one module and check if load transferred to the By Pass. If not remove the second module and check if the load transferred to the By Pass.							
Once all module in operation and no alarm. Switch on AC output breaker.							
Test on load (if available)							
ALARM							
Switch ON AC input and DC input and check that no alarm are present							
Pull out one inverter and check alarm according to redundancy							
Pull out two inverters and check alarm according to redundancy							
Switch OFF AC input (commercial power failure) and check the alarm according to the configuration							
Switch OFF DC input (DC power failure) and check that the alarm according to the configuration							
Check the different digital input according to the configuration (when used)							



Trouble Shooting and Defective Situations Fixing

14. Trouble Shooting and Defective Situations Fixing

14.1 Trouble Shooting

Inverter module does not power up: Check AC input present and in range (AC breakers)

Check DC input present and in range (DC breakers)

Check that the inverter is properly inserted

Remove inverter to verify that slot is not damaged, check connectors

Check that module(s) is (are) in OFF state

Check for loose terminations

Inverter system does not start: Check that T2S is present and properly inserted

Check remote ON/OFF terminal

Check the configuration and setting

Check threshold level

Inverter only run on AC or DC: Check AC input present and in range (AC breakers)

Check DC input present and in range (DC breakers)

Check the configuration and setting

Check threshold level(s)

No output power: Check output breaker

All OK but I have alarm: Check configuration file and correct No of modules

Download/clear log file

No output alarm: Mind the default time delay (UA: 60s, NUA: 30s)

Check configuration file

No information on CanDis: Check that T2S is present and properly inserted

Check that the RJ45 cable is connected between T2S shelf and CanDis shelf

No value on TCP/IP: Check that the RJ45 cable is connected between T2S shelf and CanDis shelf

Wait approx 2 minutes to allow the system to collect serial data.



14.2 Defective modules

Unless input power is down all LEDs on each module should be green (see section 9, page 26). No light, orange light, red or flashing light are abnormal conditions. Refer to section 10.2, page 30 to collect and record module information. If no fix can be found, replace module.

14.2.1 Replacing modules


Refer to section 11, page 31 to remove and re-insert modules.

14.2.2 Return defective T2S interface

A T2S totally dark (indication area) or that cannot interface with your laptop are evidence of failure. Proceed as per section 14.2.4, page 39.

14.2.3 Return defective shelf

The shelf is passive. Failure is unlikely to happen. In turn defective situation are barely always visible. After depose proceed as per section 14.2.4, page 39.



14.2.4 Return defective modules

- A repair request should follow the regular logistics chain: End-user => Distributor => CE+T Power.
- Before returning a defective product, a RMA number must be requested through the http://my.cet-power.com extranet. Repair registering guidelines may be requested by email at repair@cet-power.com.
- The RMA number should be mentioned on all shipping documents related to the repair.
- Be aware that products shipped back to CE+T Power without being registered first will not be treated with high priority!
- Information on failure occurrence as well as module status given through Menu 2-1 shall be attached to defective unit return package or recorded in RMA.



Service

15. Service

For Service

- Check Service Level Agreement (SLA) of your vendor. Most of the time they provide assistance on call with integrated service. If such SLA is in place, you must call their assistance first.
- If your vendor doesn't provide such assistance (*) you may call CE+T directly. Toll free Number 1(855) 669 4627(**)

Service is available from 8:00 A.M. to 10:00 P.M. EST, Monday through Friday, except closing periods for holidays or inclement weather.

Major Incidents and Emergency conditions can be invoked for immediate handling of same number or by dropping a mail on customer.support@cetamerica.com (***)

- (*) CE+T will redirect your call to your vendor if he has such SLA in place.
- (**) Valid in USA and Canada only.
- (***) Messages that are not Major Incident or Emergency will be served at the next scheduled working day.



Maintenance Task

16. Maintenance Task

As maintenance will be performed on live system, all tasks should be performed only by trained personnel with sufficient knowledge on TSI product.

Tasks:

- Identify the site, customer, rack number, product type.
- Download and save configuration file for back up.
- Check configuration file to be in accordance with operational site conditions.
- Read and save log file for back up.
- Check and analyze log file, and if alarm are present.
- Replace dust filter if present. Filter is mandatory in dusty environment.
- Check module temperature and log value. If internal temperature is higher then previous year, it should be interesting analyze if it is due an increasing load or dust effect. It is common to have a delta of 15°C by 30% of load between the ambient and the internal temperature. If temperature increase due internal dust built up, clean the module by air suction blower or vacuum cleaner.
- Clean cabinet (vacuum cleaner or dry cloth)
- Control the inverter mapping (AC Group, DC Group, Address)
- Check load level and record the rate value (print in word document the 4 screen modules information for the 32 modules, the 3 screen for the phases value and the 2 screens for the group AC and DC value)
- Change the configuration file for AC and DC mix mode to check that all TSI work on both power supply
- Check alarm operation (e.g., redundancy lost, mains failure, DC failure) on dry contact and through SNMP system or web interface.
- Switch OFF AC IN and check alarms.
- Check temperature terminal and temperature wiring. If possible use an infrared camera.
- Read and record value as wave form, power factor, Crest factor, THD I from power analyzer.
- Take cabinet picture
- Keep track of report and provide end user with a copy.
- Perform a MBP procedure. This task is not really recommended*, but could be demanded by site manager.

^{*} It is not recommended because when you perform a By-pass procedure, generally there is no back up on AC input line, and the load shutdown if mains disappear.

